

**ADDENDUM NO. 2
TO THE
PLANS AND SPECIFICATIONS
FOR
PARK IMPROVEMENTS
CHURCH STREET PARK
FOR THE
CITY OF LOOGOOTEE
MARTIN COUNTY, INDIANA**

MEI #2022115-00

Issue Date: May 9, 2024

This addendum becomes part of the Contract Documents and modifies the original Contract Documents as noted below. Acknowledge receipt of this Addendum by inserting the number and issue date of this addendum in the blank space provided on the Bid Form.

The following items shall amend, clarify, and/or correct plans and/or specifications for the above project and shall take precedence over items in conflict herein:

Item No. 1: Reference Drawings:

Plan Sheet 17, Proposed Shelter Building

Clarification:

City of Loogootee will provide the proposed steel shelter building and anchor bolts. The contractor shall install anchor bolts furnished by the City. The veneer stone and framing around all steel columns of the structure will be excluded from the project. All other work shall remain as shown in Plans and Addendum No. 1, Dated May 6, 2024.

Item No. 2: Reference Drawings:

Plan Sheet 9 & Plan Sheet 10, Demolition Plan & Plan Sheet

Clarification:

Note on Plan Sheet 9, Demolition Plan, "CITY OF LOOGOOTEE TO REMOVE 12" OF EXISTING STONE AND SOIL PRIOR TO START OF CONSTRUCTION".

Note on Plan Sheet 10, "INSTALL SOD AND A MIN. 6" OF TOPSOIL".

The note is simply stating that a minimum of 6 inches of top soil shall be provided below sod. Contractor still needs to provide all fill necessary to establish final grades as shown on plans with the intent of existing grade being 12 inches less than what is shown on Demolition Plan.

Respectfully Submitted,

MIDWESTERN ENGINEERS, INC.



Trey M. Kidwell, P.E.
Senior Project Engineer